

T99X171.00 Verify New Logo Housing issue



Foxconn Industrial Internet
富士康工业互联网

Prepare by: ME - Huy



Date: April 24th 2023

T99X171.00 Verify New Logo Housing issue (NWE VietNam)

➤ Control Run NWE Housing production in Viet Nam

❖ TOP CASE ASS'Y 95.05*95.05 (441.00896.035)

+ New housing come in material not available thermal pal , so wanted use thermal pal as old housing

P/N		Logo	In Housing	Material
441.00896.025	Old Material			ABS
441.00896.035	New Material			MABS

Sample	GAP LAN	GAP HDMI	GAP USB	GAP DC	Spec
#1	0.25	0.2	0.2	0.25	0.5mm
#2	0.2	0.2	0.2	0.2	
#3	0.2	0.2	0.25	0.2	
#4	0.25	0.25	0.25	0.2	
#5	0.25	0.2	0.2	0.25	
#6	0.2	0.2	0.25	0.2	
#7	0.25	0.25	0.25	0.25	
#8	0.25	0.25	0.2	0.2	
#9	0.2	0.25	0.2	0.2	
#10	0.2	0.2	0.2	0.25	

➤ **Summary** : Assembly 100 pcs, All 100pcs is working normal. Rate: 100.00 %

Conclusion

ME checked GAP usb, HDMI, DC, LAN all in the spec 0.5mm

OBA test function result (OBA function test 100/100 units): Pass 100%: Done : 24-April-2023

➤ Control run Result : With the results of the control run, Currently with 100pcs as pass. can use new housing of NWE

